

EPA Guidelines

**Environmental management of
landfill facilities**
(municipal solid waste and
commercial and industrial general waste)

January 2007

Erratum

The following correction has been made to the table on page 28 of these guidelines in Table 3, 'Suggested measures for leachate containment and management systems':

For the measure 'Design and construct a leachate drainage layer at Class SB+, MB-, MB+ and L sites',

'clean, hard, durable, sound gravel'

replaces the third dot point, relating to the composition of the blanket drainage medium. The text 'clean, hard, durable, sound gravel, rock or aggregate' has been replaced.

EPA Guidelines for

Environmental management of
landfill facilities
(municipal solid waste and commercial
and industrial general waste)

JANUARY 2007

EPA Guidelines for environmental management of landfill facilities (municipal solid waste and commercial and industrial general waste)

For further information please contact:

Environment Protection Authority
GPO Box 2607
Adelaide SA 5001

Telephone: (08) 8204 2004
Facsimile: (08) 8124 4670
Freecall: 1800 623 445 (non-metro callers)

Email: epainfo@epa.sa.gov.au

Web site: <www.epa.sa.gov.au>

ISBN 1 921125 34 9

January 2007

© *Environment Protection Authority*

This document may be reproduced in whole or part for the purpose of study or training, subject to the inclusion of an acknowledgment of the source and to its not being used for commercial purposes or sale. Reproduction for purposes other than those given above requires the prior written permission of the Environment Protection Authority.



Printed on recycled paper

CONTENTS

- ABBREVIATIONS iv
- 1 INTRODUCTION 1**
 - 1.1 Objectives 1
 - 1.2 Who should use this guideline? 2
 - 1.3 How will EPA use this guideline? 2
 - 1.4 Structure of this guideline 3
 - 1.5 Currency of this guideline 4
- 2 HOW TO USE THIS GUIDELINE 5**
 - 2.1 Guideline implementation schedule 6
 - 2.2 Requirements determined by landfill classification 6
 - 2.3 What sections relate to specific landfill life cycle stages? 9
 - 2.4 Additional information 12
- 3 SCREENING AND SITING OF LANDFILL FACILITIES 13**
 - 3.1 Objective 13
 - 3.2 Waste management plan 13
 - 3.3 Community issues 13
 - 3.4 Planning regulations 13
 - 3.5 Environmental considerations 14
 - 3.6 Buffer distances 14
 - 3.7 Water 15
 - 3.8 Surface water 15
 - 3.9 Groundwater 15
 - 3.10 Aboriginal and heritage issues 16
 - 3.11 Flora and fauna 16
 - 3.12 Infrastructure 17
 - 3.13 Amenity 17
 - 3.14 Unstable areas 17
- 4 SITE LAYOUT FOR LANDFILL FACILITIES 18**
 - 4.1 Objectives 18
 - 4.2 Required outcomes 18
 - 4.3 Suggested measures 18
- 5 ENVIRONMENTAL ASSESSMENT AND WATER MANAGEMENT STRATEGIES FOR LANDFILL DESIGN 20**
 - 5.1 Objective 20
 - 5.2 Required outcomes 20
 - 5.3 Suggested measures 20

5.4	Assessment of potential impacts and management strategies.....	21
6	LEACHATE CONTAINMENT AND MANAGEMENT SYSTEMS	25
6.1	Objectives.....	25
6.2	Required outcomes	25
6.3	Suggested measures	25
7	USE OF GEOSYNTHETIC MATERIALS IN BASE LINER SYSTEMS.....	31
7.1	Objectives.....	31
7.2	Required outcomes	32
7.3	Considerations related to geosynthetic liners.....	32
7.4	Suggested measures	34
8	MANAGEMENT STRATEGIES FOR LANDFILL GAS AND AIR QUALITY	38
8.1	Background to landfill gas and air quality	38
8.2	Objective.....	38
8.3	Required outcomes	38
8.4	Suggested measures	39
9	CAPPING SYSTEMS.....	42
9.1	Objectives.....	42
9.2	Required outcomes	42
9.3	Suggested measures	42
10	USE OF GEOSYNTHETIC MATERIALS IN CAPPING SYSTEMS	50
10.1	Objectives.....	50
10.2	Required outcomes	50
10.3	Considerations related to geosynthetic liners.....	51
10.4	Suggested measures	53
11	CONSTRUCTION QUALITY ASSURANCE FOR LANDFILL FACILITIES.....	57
11.1	Objective.....	57
11.2	Required outcomes	57
11.3	Suggested measures	57
12	CLOSURE AND POST-CLOSURE PLANS	61
12.1	Objectives.....	61
12.2	Required outcomes	62
12.3	Suggested measures for closure plans	62
12.4	Suggested measures for post-closure management.....	65
13	LANDFILL ENVIRONMENT MANAGEMENT PLAN (LEMP).....	67
13.2	Structural framework for the LEMP	68
13.3	LEMP review and approval—existing landfill sites and sites with development approval	73
13.4	Relevant sections in this guideline	74

14 PROPOSAL OF VARIATIONS OR DEVELOPMENT OF ALTERNATIVES TO GUIDELINE MEASURES	75
14.1 Process overview	75
14.2 Preliminary Assessment	76
14.3 Development and agreement of performance parameters and process	76
14.4 Prepare application for alternative	78
14.5 Submit application for assessment	78
14.6 Examples	79
15 REFERENCES AND DEFINITIONS	82
15.1 References	82
15.2 Waste type glossary and definitions	84
16 ATTACHMENTS	86
16.1 Attachment 1—Examples of landfill classification for design of landfill facilities	86
16.2 Attachment 2—Potential for leachate generation based on climatic conditions	88
16.3 Attachment 3—Technical guidance for assessment of materials and methodology for construction of clay liners	89
16.4 Attachment 4—CQA minimum requirements	91
16.5 Attachment 5—Minimum properties for various geosynthetic lining materials for base liner systems	92
16.6 Attachment 6—Minimum properties for various geosynthetic lining materials for caps	93

ACKNOWLEDGEMENTS

The assistance of the following organisations and individuals in developing this landfill guideline is gratefully acknowledged:

- all respondents who provided valuable feedback during the consultation process that informed the development of this guideline
- Waste Definitions Working Group (Waste Management Association of Australia/EPA and other agencies).
- Golder Associates
- Tonkin Consulting
- REM Resource and Environmental Management
- GHD Pty Ltd
- Anthony Lane, Lane Consulting
- Warnken ISE
- Jamie VanGulck, Assistant Professor Geoenvironmental Engineering, University of Manitoba, Canada

ABBREVIATIONS

AWWA	American Water Works Association
CQA	Construction Quality Assurance
EIS	Environmental Impact Statement
EPA	Environment Protection Authority (South Australia)
EPP	Environment Protection Policy
ISO	International Standards Organisation
LEMP	Landfill Environment Management Plan
LFG	Landfill Gas
MRRF	Materials Resource Recovery Facility
QA	Quality Assurance

